

ADDENDUM No. 2
Request for Competitive Sealed Proposals (CSP)
19CSP088 Akins High School Weight Room & Athletic Field
Improvements

January 2, 2019

Item 1: Questions and Answers -Full Attachment found [at planroom.millerids.com](http://planroom.millerids.com)

Item 1:

Q: Please verify if the Duct Detector shown at RTU-31 should be installed within the Supply Side per Austin Fire Department requirements.

A: It should be in the supply air.

2. Q: Please verify if duct detectors are required within 5 feet of the (2) Fire Smoke Dampers per IMC 2015 607.3.3.2.1.

A: This is City of Austin, IMC shouldn't apply.

3. Q: Please note that an SD Duct Detector should be provided with a minimum of 12" wide duct for sampling.

A: This is installation requirement issue, not a design issue.

4. Q: Please verify that per the specifications these are to be Silent Knight 4-wire SD505-DuctR detectors which replace the Specified SD-505ADHR.

A: Agreed, SD505-DuctR.

5. Q: Please verify that these detectors should be powered by existing or new UL listed Fire Alarm Power Supplies with required battery backup.

A: Agreed.

6. Q: Please verify if Remote Test Switches Type SD505-RTS should be provided for each duct detector.

A: Agreed, remote test switches are required.

7. Q: Please verify the Wage Determination Date for this project.

A: Wage Determination date is 10/19/2018

General Decision Number: TX180323 10/19/2018 TX323

Superseded General Decision Number: TX20170323

State: Texas

Construction Type: Building

County: Travis County in Texas.

BUILDING CONSTRUCTION PROJECTS (does not include single family homes or apartments up to and including 4 stories).