



ADDENDUM No. 1
Request for Competitive Sealed Proposals (CSP)
20CSP046 MEP Improvements at Ortega Elementary School

November 20, 2019

Received by bidder:

Date: _____

Name: _____


Signature: _____

Item 1: Changes to Project Manual

Changes to the Project Manual are attached below.

Item 2: Change in HUB Coordinator

The HUB coordinator assigned to this project is now Melfi Penn who can be reached at melfi.penn@austinisd.org



ADDENDUM NUMBER ONE (1)

AUSTIN ISD PROJECT 20-0021-ORTGA
RENOVATIONS AT ORTEGA ELEMENTARY SCHOOL
November 19, 2019

The Contract Documents and Specifications for the above referenced project are amended and revised as indicated in this Addendum. Any proposal submitted in response to the invitation to the bidders shall be prepared accordingly. Receipt of Addendum is to be acknowledged on contractor's proposal.

ITEM #1, Rooftop Condensing Unit Support Clarification

- A. Equipment support pads, struts, cross-members and platforms as detailed in 2/R-2.0 shall be engineered by the manufacturer based on approved equipment submittals.

ITEM #2, Packaged DX RTU Clarification

- A. Specifications section 238119, paragraph 2.6.A.1 references variable speed compressor "where called for on the drawings." Scheduled RTU-LIB for this project is only required to have (minimum) 2-stage compressor. 238119 paragraph 2.6.A.1 is not applicable.

ITEM #3, IDU-LIB condensate pump power

- A. At IDU-LIB (reference sheet E4.1 and coordinate with mechanical), provide additional 15A/1P circuit and 2-#12, #12G from new panel P1 to new GFI receptacle for condensate pump (pump by mechanical).

ITEM #4, Panel 'SD1' wall paint scope

- A. Upon removal of existing panel 'SD1' and associated devices (reference 1/E4.2, room '200 BKRM'), contractor shall paint the entire wall where electrical panels have been replaced. That shall include the entire wall from inside corner at the south of the room to the inside corner at the north end and from floor to ceiling. Painting shall include one coat of primer and two coats of paint. Sherman Williams Promar shall be the standard. Color as selected by Architect.

END.